



## **Addendum #1**

### Bid Number 23/24-20 Various Sites CAT 6 Cabling for IP Phone Project

The changes made under this Addendum of the Contract Documents, Specifications, Special Provisions, and Plans for the above project Bid Packet are as follows:

#### **Item 1. Pre-Bid RFIs**

1. Section 01 1100 Summary of Work 1.02.B states, "Run CAT 6 cable from IDF rooms on sites to the classrooms". From this morning's job walk, it's apparent there are more locations that need CAT 6 that just the classrooms. Please provide a total count per site for the number of drops needed. **Addendum 1 updated documents addresses the additional locations and drop count per site.**
2. Is there a Project Labor Agreement (PLA) in place for this project? **No.**
3. Please confirm that the existing CAT 3 and faceplate are to remain operational, and their demo is not part of this scope of work. **Correct.**
4. Please confirm one (1) CAT 6 cable only is required per drop. **Correct.**
5. Please confirm no patch cords are required for this project. **District will provide patch cords if/when needed.**
6. Please confirm a service loop of approximately 10' is required above each drop and the new CAT 6 jack will be left in the same box, behind the existing CAT 3 jack. The existing CAT 3 drops are not to be demoed but shall remain operational at the completion of this project. **Correct.**
7. Please confirm a patch panel shall be provided at each IDF to terminate the new drops. **Patch panel shall be provided by the contractor to terminate new drops in the IDFs.**
8. Please confirm all work is to be done during 2nd shift. **Correct.**
9. Please confirm all pathway is existing and is to be reused. **Correct.**
10. Section 00 7100 Special Conditions 7 Insurance Policy Limits, states that "Commercial General Liability shall have \$4,000,000.00 general aggregate" and "Excess Liability (Umbrella) shall have \$6,000,000.00 aggregate". Please confirm these amounts are correct, and that they are required for this project along with the other stated insurance limits. **Correct.**
11. RFP mentions running a (1) new cat 6 cable in each classroom for IP phones. During the job walk it was noticed that there might some rooms/locations that may need more than (1) cable run. Can you please provide such locations at each site? **Addendum 1 updated DIV 01 and plans indicated added locations and total drops per site.**



12. Are there any locations apart from the classrooms that may need a cable run for IP Phones? If yes, please provide a list of all such locations at every site. **Addendum 1 updated DIV 01 and plans indicated added locations and total drops per site.**
13. Can you please provide a total number of drops needed at each site? **Addendum 1 updated DIV 01 and plans indicated added locations and total drops per site.**
14. It was discussed during the job walk that the new cat 6 cable needs to be terminated into a jack which should be left inside the existing box. Please confirm that no faceplates, surface mount boxes etc. are required to be installed in this project. **Correct.**
15. How many sites would need a lift for high ceilings to run the new cable? **Most elementary sites with a cafeteria.**
16. Will the contractor be allowed to work at multiple sites simultaneously? **Yes.**
17. It was discussed during the job walk that the 2 storied building at Sussman Middle School already has upgraded cabling and hence would need to be eliminated from scope for this project. Please confirm how many drops to be eliminated? **Addendum 1 updated DIV 01 and plans indicated added locations and total drops per site.**
18. Please provide a list and quantity of locations that will be eliminated from this project scope due to already upgraded cabling. **Addendum 1 updated DIV 01 and plans indicated added locations and total drops per site.**
19. For bidding purposes, please confirm that the contractor is expected to terminate new cables in CFCI patch panels. **Not needed.**
20. Do most sites have T-bar ceiling or hard-lid ceiling? **Most sites are T-bar ceiling.**
21. Are there any locations that will need OSP cables? If yes, how many? **No OSP Cables needed.**

## **Item 2. Contract Documents**

1. Please replace DIV 01 and site plans with the attached – updated details on scope of work per job walk and total number of drops per site.

END OF DOCUMENT